BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI

Office of the Executive Engineer Dasarahalli Division,

SCHEDULE-B

NAME OF WORK: Improvements CC Roads Near Sree Rama Temple area in Mallasandra Ward No.13, Shettyhalli Sub Division.

Sl. No	Description of work	Unit	Qty	Sanctioned Estimate Rates	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 1.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods Complete as per specification and direction of Engineer-in-charge of the work.	Cum	119.52	105.84	Rupees One Hundred Five and Eighty Four Paise Only
2	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery Complete as per specification and direction of Engineer-in-charge of the work.	Cum	58.14	5070.60	Rupees Five Thousand Seventy and Sixty Paise Only
3	Providing and laying cement concrete using 20 mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete (RMC) M 20 for R.C.C works laid in 15 cms thick layers and well compacted vibrating, curing, for raft foundation column footing, main and secondary beams with all lead and lifts etc., Complete as per specification and direction of Engineer-in-charge of the work.	Cum	242.43	6332.04	Rupees Six Thousand Three Hundred Thirty Two and Four Paise Only
4	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 10 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading Complete as per specification and direction of Engineer-in-charge of the work.	Cum	119.52	75.47	Rupees Seventy Five and Forty Seven Paise Only

EXECUTIVE ENGINEER-4
BRUHAT BANGALORE MAHANAGARA PALIKE
BENGALURU-560 010

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,